

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92
EE/BTP/TEN/02/2012-13 D: 15.05.2012

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No. 144

Name of the work: Providing RCC Road to Doddabommasandra old Village and Anantharam House Road in Ward No. 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	735.00	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200 m (within average thickness of 15 cms), Page No. 273 / Item No. 37.51 PWD SR 2013-14	Sqm	Rs.43.20	
2	153.00	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 Page No. 152 / Item No. 19.2/ PWD SR 2013-14	cum	Rs.90.72	
3	153.00	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No. 12 / Item No. 4.3 PWD SR - 2013-14	m	Rs.4,290.84	
4	95.00	KSRRB M2600-3: Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, No. 251 / Item No. 31.3 PWD SR 2013-14	cum	Rs.137.16	
5	102.00	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. Page No. 19 / Item No. 4.48.1/ PWD SR 2013-14	Cum	Rs.6,464.88	
6	1020.00	Vaccum De-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift No. 190 / Item No. 22.7/ PWD SR 2013-14	Cum	Rs.91.80	

Signature of the Contractor

ಕರಡು ಬೆಂಡರ್ ಪೆಡ್ಕೊಲನ್ನು ತಿದ್ದು ಪಡಿ ಮಾಡಿದಂತೆ/
ತಿಗಲಾ ಇಲ್ಲದ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಕಂಪೆ. N12

Page 1 of 2
Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

31/10/2013